

अल्पकालीन कोटेशन आमंत्रण सूचना-सं0-07/BIADA/2017-18

उद्योग भवन के उपरी तल पर Lift के दरवाजे पर Shed, Brick Work demolishing एवं भवन के पिछले प्रवेश द्वार पर Portico का कार्य हेतु कोटेशन आमंत्रित किया जाता है। यह कोटेशन कार्यपालक अभियंता, बिद्याडा पटना, प्रथम तल उद्योग भवन, पूर्वी गाँधी मैदान के कार्यालय में दिनांक 18.08.2017 के अपराह्न 3:00 बजे तक प्राप्त किया जाएगा तथा दिनांक 18.08.2017 के 3:30 बजे अपराह्न में कोटेशनदाताओं या उनके अधिकृत प्रतिनिधियों के समक्ष तकनीकी बीड एवं वित्तीय बीड खोला जाएगा।

एजेन्सी का नाम एवं पता

कार्य की विवरणी

Name of Work:- Construction of Portico & Demolishing Brick Pillar (Top Roof of Udyog Bhawan BIADA, Patna.

Sl. No	Description of items	Unit	Quantity	Rate		Amount
				In Word	In Figure	
1	Making 25 cm (10") dia bore up to 4.5 below ground with hand auger of approved quality in ordinary soil(vide classification of soil item - A) true to plum and without eccentricity in any stage of operation and disposal of the excavated earth up to 50 m lead including all lifts all complete as per approved design and direction of E/I.	mtr	6.00			
2	Making 63 cm (25") dia under ream at required depth with hand Rimmer of approved quality in ordinary soil (vide classification of soil item - A) true to plum and without eccentricity in any stage of operation and disposal of the excavated earth up to 50m lead including all lifts all complete as per approved design and direction of E/I.	nos	2.00			
3	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material withing 50 metres lead:	Cum	0.197			
4	Earth work in excavation in foundation trenches of drain (not excoding 1.5m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m,including getting out the excavted soil and disposal of surplus excavated soil as and disposal of surplus soil within 50 meter lead.					
	All Kinds of soil	Cum	2.25			
5	Supplying and Filling in plinth with local sand and under floors including, watering, ramming consolidating and dressing complete.	Cum	0.22			

6	Providing designation 100 A one brick on flat soling joints filled with local sand including cost of watering, taxes, royalty all complete as per building specification and direction of E/I	sqm	2.83				
7	Providing and laying in position cement concrete specified grade of reinforced excluding the cost of centring and shuttering						
	1:2:4 (1 Cement: 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	Cum	0.120				
8	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work up to Plinth level.1:1.5:3 (1 cement :1.5 coarse sand :3 graded stone aggregate 20mm nominal size)						
	1:1.5:3 (1 Cement: 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	1.47				
9	Providing and laying in position specified grade of Reinforced cement concrete work in wall (any thickness),including attached pilasters, buttresses, plinth and string coursed, fillets, columns, pillars, piers, abutments, posts and struts, etc. Up to floor five level excluding cost of centring, shuttering, finisnin and reinforcement.						
	1:1.5:3 (1 Cement: 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	Cum	0.29				
10	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 150 landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1;2:4(1 cement: 2 coarse sand: 4 graded stone aggregate 20mm nominal size).	Cum	1.20				
11	Centering and shuttering including strutting propping etc. and removal of form work.						
	Foundations,footings, bases Columns.	sqm	6.47				
	Suspended floors,roof,landing,balconies and access platform.	sqm	11.75				
	Columns,Pillars, Piers, Abutments, Posts and Struts	sqm	4.78				
12	Reinforcement for RCC. Work including starightening, cutting,bending,placing in position and binding all complete.						

A	Thermo-Mechanically Treated bars TMTC-500-8 mm dia		Kg	39.46			
B	Thermo-Mechanically Treated bars TMTC-500-10 mm dia		Kg	111.50			
C	Thermo-Mechanically Treated bars TMTC-500-12 mm dia		Kg	89.80			
13	Brick work with bricks of class designation 100A in foundation and plinth.						
	Cement mortar 1 :4 (1 cement: 4 coarse sand)		Cum	0.180			
14	12mm cement plaster of mix:						
	1:4(1 cement: 4 coarse sand)		sqm	17.89			
15	Finishing walls with water proofing cement paint of approved brand and manufacture and of required shade to give an even shade.New work (three or more coats).		Sqm	17.89			
16	Structural steel work riveted or bolted in built up section,trusses and framed work,including cutting,hosting,fixing in position and applying a priming coat of approved ayeef primer all complete		Kg	80.00			
17	Providing corrugated G.S. sheet roofing fixed with G.I.J. or hooks, bolts and nuts 8 mm diameter with bitumen and G. I. limpet washers or with G.I. limpetwashers filled with white lead and including a coat of approved steel primer and two coats of approved paint on over lapping of sheets complete (upto a pitch of 60°) excluding the cost or purlins, rafters and trusses.						
	0.8mm thick with zinc coating not less than 275 gm/m2		Sqm	4.87			
18	Demolishing brick work including stacking of serviceable material and disposal of unserviceable material within 50 meters lead:						
	In cement mortar		Cum	28.25			
19	Providing and laying in situ seven course water proofing treatment with APP (Atactic polypropytene)modified polymeric memberence over roof consisting of first coat of bitumen primer @ 0.4 kg per sqm,2nd,4th & 6th courses of bonding material @ 1.20 kg/ sqm,which shall consist of blown type bitumin of grade 85/25 conformingn t is:702,3rd and 5th layers of roofing membrance APP modified Polymeric		Sqm	225.00			

	membrane 2.0mm thick of 3.00 kg/sqm weight consisting of five layers prefabricated with center core as 1 OOmicon HMHDPE film sandwiched on both sides with polimeric mix and the polymeric mix is protected on both sides with 20 micron HMHDPE film. 7th, the top most layers shall be finished with brick tiles of class designation 100 groted with cement mortar 1:3 (1cement: 3 fine sand) mixed with 2% integral wqter profing compound by weight of cement over a 1222 layer of cement mortar 1:3 (1 cement:3 gine sand) and finished neat which shall be paid for separately.				
20	Skilled Beldar (for floor rubbing etc.) / Grinder	Nos	18.00		
21	Supply and Fabrication & erection of 24G GSS ducting	Sqm	11.45		
22	Supply and fixing of vanvass connection and volume control damper	Nos	1.00		
23	Carriage of Materials				
A	Stone Chips (102 km Gaya by Road)	Cum	2.760		
B	Coarse Sand (45 km Koilwar by Road)	Cum	1.70		
C	Brick (8 km)	%nos	0.18		
D	Local Sand (3 km)	Cum	0.25		
			Total Amount Rs.		

विशेष शर्त :-

- कोटेशन की शर्त एवं दर उद्धृत किये जाने वाले Format बियाडा के वेबसाईट www.biadabihar.in पर देखें एवं प्रकाशित Format पर ही दर उद्धृत करें।
- तकनीकी बीड एवं वित्तीय बीड का लिफाफा एक साथ ही दर लिखकर डालना होगा जो एक बड़े लिफाफे के अन्दर बन्द रहेगा।
- कोटेशनदाताओं को अपना दर अंक एवं शब्दों में उद्धृत करना होगा।
- कोटेशन कागजात के सभी पन्नों पर पृष्ठ संख्या एवं एजेन्सी की मुहर के साथ अधिकृत व्यक्ति का हस्ताक्षर तिथि सहित अनिवार्य होगा।
- कार्य की मात्रा कम या अधिक हो सकती है। दर प्रति ईकाई तथा अंक एवं शब्दों में उद्धृत करना अनिवार्य होगा।
- सशर्त कोटेशन स्वीकार नहीं की जाएगी।
- कोटेशनदाताओं को निबंधन प्रमाण पत्र, /सूची वद्धता प्रमाण पत्र, पैन नं० एवं जी०एस०टी० की अभिप्रमाणित प्रति तकनीकी बीड के साथ संलग्न करना अनिवार्य होगा।
- सफल निविदादाता को बियाडा के नियमानुसार एकरारनामा करने के उपरान्त कार्य आवंटन आदेश निर्गत किया जायेगा।
- कार्य समाप्ति की अवधि 15 दिन होगी।
- कोटेशनदाता कोटेशन डालने से पूर्व कार्य स्थल से भली-भाँती अवगत हो लें।
- अधोहस्ताक्षरी या विभागीय सक्षम पदाधिकारी को बिना कारण बताये कोटेशन रद्द करने का अधिकार सुरक्षित होगा।

ह०/-

ज्ञापक 3800/1998

866/Engg/BIADA/P-94/17

दिनांक

17/02/17

प्रतिलिपि:- प्राधिकार के सूचना पट्ट पर प्रकाशित किये जाने हेतु प्रेषित / आई० टी० पदाधिकारी को प्राधिकार के वेब साईट पर प्रकाशित किये जाने हेतु प्रेषित / प्रबंध निदेशक के विशेष कार्य पदा०-सह जन सम्पर्क पदा० को सूचनार्थ प्रेषित।

कार्यपालक अभियंता,
बियाडा, पटना।

कार्यपालक अभियंता