

अल्पकालीन कोटेशन आमंत्रण सूचना-सं0-11/BIADA/2017-18

औद्योगिक क्षेत्र, हाजीपुर में शाखा कार्यालय के पीछे अवस्थित खाली जगह/सड़क के घेराबंदी का कार्य हेतु कोटेशन आमंत्रित किया जाता है। यह कोटेशन कार्यपालक अभियंता, बियाडा पटना, प्रथम तल उद्योग भवन, पूर्वी गाँधी मैदान के कार्यालय में दिनांक 31.10.2017 के अपराह्न 3:00 बजे तक प्राप्त किया जाएगा तथा दिनांक 31.10.2017 के 4:30 बजे अपराह्न में कोटेशनदाताओं या उनके अधिकृत प्रतिनिधियों के समक्ष तकनीकी बीड एवं वित्तीय बीड खोला जाएगा।

एजेन्सी का नाम एवं पता

कार्य की विवरणी

| Name of Work:- Construction of Boundary Wall At – Industrial Area Hajipur. | | | | | | |
|--|---|-------------|----------|---------|-----------|--------|
| Sl.No | Description of items | Unit | Quantity | Rate | | Amount |
| | | | | In Word | In Figure | |
| 1 | Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rebbies, lead up to 50m and lift up to 1.5 m | | | | | |
| | All kinds of soil. | 100/S qm | 80.50 | | | |
| 2 | Making 25 cm (10") dia bore up to 4.5 below ground with hand auger of approved quality in ordinary soil(vide classification of soil item - A) true to plum and without eccentricity in any stage of opration and disposal of the excavated earth up to 50 m lead including all lifts all complete as per approved design and direction of E/I. | mtr | 57.95 | | | |
| 3 | Making 63 cm (25") dia under ream at required depth with hand Rimmer of approved quality in ordinary soil (vide classification of soil item - A) true to plum and without eccentricity in any stage of operation and disposal of the excavated earth up to 50m lead including all lifts all complete as per approved design and direction of E/I. | nos | 19.00 | | | |
| 4 | Supplying and filling in plinth with local sand under floors including, watering, ramming consolidating and dressing complete. | Cum | 60.25 | | | |
| 5 | Providing designation 100 A one brick on flat soling joints filled with local sand including cost of watering, taxes, royalty all complete as per building specification and direction of E/I. | Sqm | 10.06 | | | |
| 6 | Providing and laying in position cement concrete specified grade of reinforced excluding the cost of centring and shuttering All work up to Plinth level. | | | | | |
| | 1:4:8 (1 Cement: 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) | Cum | 0.89 | | | |

| | | | | | | |
|----|---|-----|--------|--|--|--|
| 7 | Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement - All work up to Plinth level.1:1.5:3 (1 cement :1.5 coarse sand :3 graded stone aggregate 20mm nominal size) | Cum | 7.39 | | | |
| 8 | Providing and laying in position specified grade of Reinforced cement concrete work in wall (any thickness),including attached pilasters, buttresses, plinth and string coursed, fillets, columns, pillars, piers, abutments, posts and struts, etc. Up to floor five level excluding cost of centring, shuttering, finisnin and reinforcement.1:1:5:3 (1 cement :1.5 coarse sand 0.3 graded stone aggregate 20mm nominal size) | Cum | 2.25 | | | |
| 9 | Reinforced cement concrete work in beams, suspended floors,roofs having slope up to 15, landings, balconies, shelves,chajjas,lintels, bands,plain window sills,staircases and spiral stair cases up to floor five level excluding the cost of centring, shuttering, finishing and reinforcement with 1:2:4(1 cement:2 coarse sand:4 graded stone aggregate 20mm nominal size) | Cum | 2.40 | | | |
| 10 | Bricks work with brickof class designation 100A in Superstructure.above plinth level up to floor v cum Cement 1:4 (1 cement : 4 coarse sand) | Cum | 16.86 | | | |
| 11 | Reinforcement for RCC. Work including starightening, cutting,bending,placing in position and binding all complete | | | | | |
| A | Thermo-Mechanically Treated bars TMTC-500-8mm dia | Kg | 410.03 | | | |
| B | Thermo-Mechanically Treated bars TMTC-500-10mm dia | Kg | 150.11 | | | |
| C | Thermo-Mechanically Treated bars TMTC-500-12mm dia | Kg | 605.46 | | | |
| 12 | Cement plaster in coarse sand 12 mm Cement plaster of mix.1:4(1 cement : 4 coarse sand) | Sqm | 211.30 | | | |
| 13 | Finishing walls with water proofing cement paint of approved brand and manufacture and of required shade to give an even shade.New work (three or more coats). | Sqm | 211.30 | | | |
| 14 | Centering and shuttering including strutting propping etc. and removal of form work. | | | | | |
| A | Lintels, beams, plinth beam, girders, ressumers and cantilever. | Sqm | 44.27 | | | |
| B | Stiffners, column, pillars, piers, Abutment | Sqm | 144.40 | | | |

| | | | | | |
|----|----------------------------------|----------|-------|-------------------------|--|
| 15 | Carriage of Materials | | | | |
| A | Stone Chips(120 Km,Gaya by Road) | Cum | 11.63 | | |
| B | Coarse Sand(58 Km,Koilwar) | Cum | 14.36 | | |
| C | Bricks- (8 KM) | Per %nos | 8.754 | | |
| D | Local Sand (3KM) | Cum | 60.25 | | |
| | | | | Total Amount Rs. | |

विशेष शर्त :-

- कोटेशन की शर्त एवं दर उद्धृत किये जाने वाले Format बियाडा के वेबसाईट www.biadabihar.in पर देखें एवं प्रकाशित Format पर ही दर उद्धृत करें।
- तकनीकी बीड एवं वित्तीय बीड का लिफाफा एक साथ ही दर लिखकर डालना होगा जो एक बड़े लिफाफे के अन्दर बन्द रहेगा।
- कोटेशनदाताओं को अपना दर अंक एवं शब्दों में उद्धृत करना होगा।
- कोटेशन कागजात के सभी पन्नों पर पृष्ठ संख्या एवं एजेन्सी की मुहर के साथ अधिकृत व्यक्ति का हस्ताक्षर तिथि सहित अनिवार्य होगा।
- कार्य की मात्रा कम या अधिक हो सकती है। दर प्रति ईकाई तथा अंक एवं शब्दों में उद्धृत करना अनिवार्य होगा।
- सशर्त कोटेशन स्वीकार नहीं की जाएगी।
- कोटेशनदाताओं को निबंधन प्रमाण पत्र, / पै नं.0 एवं जी0एस0टी0 की अभिप्रमाणित प्रति तकनीकी बीड के साथ संलग्न करना अनिवार्य होगा।
- सफल निविदादाता को बियाडा के नियमानुसार एकरारनामा करने के उपरान्त कार्य आवंटन आदेश निर्गत किया जायेगा।
- कार्य समाप्ति की अवधि 20 दिन होगी।
- कोटेशनदाता कोटेशन डालने से पूर्व कार्य स्थल से भली-भाँती अवगत हो लें।
- अधोहस्ताक्षरी या विभागीय सक्षम पदाधिकारी को बिना कारण बताये कोटेशन रद्द करने का अधिकार सुरक्षित होगा।

ह०/-

कार्यपालक अभियंता,

बियाडा, पटना।

ज्ञापक

1872/099

859/Engg/BIADA/P-93/17

दिनांक

30/10/17

प्रतिलिपि:- प्राधिकार के सूचना पट्ट पर प्रकाशित किये जाने हेतु प्रेषित / आई0 टी0 पदाधिकारी को प्राधिकार के वेब साईट पर प्रकाशित किये जाने हेतु प्रेषित / प्रबंध निदेशक के विशेष कार्य पदा0- सह जन सम्पर्क पदा0 को सूचनार्थ प्रेषित।

कार्यपालक अभियंता
बियाडा, पटना।