

अल्पकालीन कोटेशन आमंत्रण सूचना-सं0 10/2014-15

उद्योग भवन के उपरी तल पर Lift No- 1 एवं Lift No- 2 के दोनो लोहे का दरबाजा निर्माण काय एवं मरम्मति काय हेतु कोटेशन आमंत्रित किया जाता है। यह कोटेशन कार्यपालक अभियंता, बियाडा पटना, प्रथम तल उद्योग भवन, पूर्वी गाँधी मैदान के कार्यालय में दिनांक 16.02.2015 के अपराहन 3:00 बजे तक प्राप्त किया जाएगा तथा दिनांक 16.02.2014 के 3:30 बजे अपराहन में कोटेशनदाताओं या उनके अधिकृत प्रतिनिधियों के समक्ष तकनीकी बीड खोला जाएगा।

कार्य की विवरणी

ABSTRACT OF COST						
Name of work- Steel Gate for Lift Room, at Udyog Bhavan, Patna						
Sl.No	Description of items	Unit	Quantity	Rate		Amount
				In Word	In Figure	
1	Providing and fixing 1 mm thick M.S. sheet door with frame of 40x40x6 mm angle iron and 3mm MS gusset plate at the junction and corners,all necessary fittings complete including applying a priming coat af approved steel primer	Sqm	5.74			
2	Painting with ready mixed paint of approved brand and manufacture in all shades to give an even shade.					
	New steel work(two or more coats)	sqm	11.48			
3	Dismantling aluminum /Gypsum partitions, doors, windows, fixed glazing and false ceiling included disposal of unserviceable surplus material and stacking of serviceable material with in 50m lead as directed by E/I.	sqm	53.00			
4	Providing and fixing at all height false ceiling of 12.5 mm thick tapered edge gypsum board conforming to IS :2095 including providing and foixing of frame work made of special sections power pressed from M.S.sheet and galvanised in accordance with zinc coating 600 as per IS : 277 and consisting of angle cleats of size 25 mm wide x 16 mm thick with flanges of 22 mm and 27 mm at 1200 mm centre to centre one flange fixed to the ceiling with dash fastner 12.5 mm dia x 40 mm long with 6 mm dia botts to the angle hangers of 25x25x5 mm of required length, and other end of angle hanger being fixed with nut and botts to rate of 1200 mm centre to centre to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having clips of 10.5 mm at 450 mm centre to centre shall be be fixed in a dirction perpendicular to G.I. channel with	sqm	53.00			

	connecting clips made out of 2.64 mm dia X 230 mm long G.I. wire at every junction including but excluding the cost of painting.					
5	cement plaster in course sand. 12mm cement plaster of mix:					
	1:4(1cement :4 corse sand)	sqm	22.500			
6	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade.					
	New work(two or more coats) over and including priming coat with cement primer.	Sqm	75.00			
7	Providing and applying plaster of paris putty of 2mm thickness over plastered surface to prepare the surface even and smooth complete.	Sqm	53.00			
8	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering -all work upto plinth level.					
	1:1.5:(1cement :1.5 corse sand:3 aggregate 20mm)	Cum	0.93			
9	Providing and fixing on wall face unplasticised -PVC(working pressure 4 kg per sqm) rain water pipes confoming to(IS:4985 including jointing with seal ring conforming to IS:5382 leaving 10mm gap for thermal expansion.					
	75 mm diameter	metre	12.00			
				Total Amount -		

विशेष शर्त :-

- कोटेशन की विशेष शर्तों एवं दर उद्धृत किये जाने वाले **Format** बियाडा के वेबसाइट "www.biadabihar.in" पर देखें एवं प्रकाशित **Format** पर ही दर उद्धृत करें।
- तकनीकी बीड एवं वित्तीय बीड का लिफाफा एक साथ ही दर लिखकर डालना होगा जो एक बड़े लिफाफे के अन्दर बन्द रहेगा।
- अद्योहस्ताक्षरी या विभागीय सक्षम पदाधिकारी को बिना कारण बताये कोटेशन रद्द करने का अधिकार सुरक्षित होगा।
- कार्य की मात्रा कम या अधिक हो सकती है।
- कोटेशनदाताओं को अपना दर अंक एवं शब्दों में उद्धृत करना होगा।
- सफल कोटेशनदाता को कार्य आवंटन से पूर्व लागत मुल का 2 प्रतिशत की राशि **Security** के रूप में जमा करना होगा।
- कोटेशनदाताओं को निबंधन, पन नं., लेबर लाईसेंस, आचरण प्रमाण-पत्र की अभिप्रमाणित प्रति तकनीकी बीड के साथ संलग्न करना अनिवार्य होगा।
- कोटेशनदाता को कोटेशन के साथ संलग्न कागजात के प्रत्येक पृष्ठ पर अपना हस्ताक्षर करना होगा।
- कार्य समाप्ति की अवधि एक माह होगी।
- कोटेशनदाता कोटेशन डालने से पूर्व स्थल से भली-भाँती अवगत हो लें।

ह०/—
कार्यपालक अभियंता
बियाडा, पटना।